



ADDENDUM

03 | 200311

Penn-Delco School District

Secure Entry and Nurse Addition at
2881 Pancoast Avenue, Aston, PA 19014

Date of Addendum: 11 March, 2020

Marotta/Main Architects Project No.
18-PDSD-03

The original Project Manuals and Drawings dated 05 February, 2020 for the project noted above, are amended as noted in this Addendum No. 03

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space provided on the Bid Form.

This Addendum consists of 02 Pages and all attachments listed.

LEGAL SPECIFICATIONS:

03.01 Refer to Specification Section 01 21 00 ALLOWANCES, and MODIFY the following quantities:

26A: Reduce to four (4).

26B: Reduce to four (4).

27A: Reduce to four (4).

28A: Reduce to four (4).

28B: Reduce to one (1).

SITE / CIVIL DRAWINGS:

03.02 Refer to Sheets C-04 and detail on Sheet C-05, and decrease the infiltration bed at tennis courts from 115.5'x15.0'x3.0' to 65.0'x15.0'x3.0'.

03.03 Refer to Sheet C-04 and Sheet C-05: Decrease perforated pipe length within bed from 113.5' to 63.0' feet.

03.04 Refer to Sheet C-05: The 2'x2' inlet box located within bed changed to 8" diameter PVC/HDPE clean-out with cap.

03.05 Refer to Sheet C-07:

- a. Decrease permanent diversion channel located on the west side of the tennis courts in length from 125' to 50'. All construction items related to the installation of the channel decreased accordingly.
- b. Decrease the 12" diam. silt sock at tennis courts in length from 287' to 103'.
- c. Decrease the construction barrier fencing length from 290' to 111'.

- d. Adjust the limit of disturbance at tennis court area from 16,900 SF to 9,500 SF. Quantities associated with the stripping and replacing of topsoil and temporary and permanent stabilization are decreased accordingly.

END OF ADDENDUM 03

Respectfully Submitted,

Christopher Peters, AIA
Marotta/Main Architects, Inc.

Attachments:

- none